

TABLE OF CONTENTS

SECTION 10

DEFINITIONS

10.1 DEFINITIONS..... 10-1

SECTION 11

PLAN REVIEW, APPROVAL, CONSTRUCTION, AND ACCEPTANCE OF WATER AND WASTEWATER IMPROVEMENTS

11.1 PLANS AND SPECIFICATIONS..... 11-1

11.1.1 GENERAL..... 11-1

11.1.2 MASTER PLAN..... 11-1

11.1.3 PLAN AND PROFILE..... 11-1

11.1.4 DETAILS..... 11-2

11.1.5 SCALE..... 11-2

11.2 SUBDIVISION RELATED WATER AND WASTEWATER IMPROVEMENTS 11-3

11.2.1 GENERAL..... 11-3

11.2.2 DESIGN AND PLAN REVIEW 11-3

11.2.3 CONSTRUCTION INSPECTION 11-3

11.2.4 APPROVAL AND ACCEPTANCE..... 11-3

11.3 WATER AND WASTEWATER IMPROVEMENTS ASSOCIATED WITH THE CITY OF MASCOTTE SITE DEVELOPMENT ORDINANCE..... 11-3

11.3.1 GENERAL..... 11-3

11.3.2 DESIGN AND PLAN REVIEW 11-3

11.3.3 CONSTRUCTION INSPECTION 11-3

11.3.4 MAINTENANCE, MATERIALS, AND WORKMANSHIP WARRANTY BOND 11-4

11.3.5 CERTIFICATE OF COMPLETION/APPROVAL FOR COMPLETION..... 11-4

11.4 MISCELLANEOUS WATER AND WASTEWATER IMPROVEMENTS 11-4

11.5 COMPLIANCE WITH OTHER REGULATORY REQUIREMENTS..... 11-5

11.6 RECORD DRAWINGS..... 11-5

11.7 LIST OF MATERIALS AND APPROVED

MANUFACTURERS.....	11-5
--------------------	------

SECTION 20

GRAVITY SEWERS

20.1	GENERAL CONSIDERATIONS	20-1
20.1.1	<u>TYPE OF SEWERS</u>	20-1
20.1.2	<u>DESIGN PERIOD</u>	20-1
20.1.3	<u>LOCATION</u>	20-1
20.2	DESIGN BASIS.....	20-1
20.2.1	<u>AVERAGE DAILY FLOW</u>	20-1
20.2.2	<u>PEAK DESIGN FLOW</u>	20-2
20.2.3	<u>DESIGN CALCULATIONS</u>	20-2
20.3	DETAILS OF DESIGN AND CONSTRUCTION.....	20-2
20.3.1	<u>MINIMUM SIZE</u>	20-2
20.3.2	<u>MINIMUM COVER</u>	20-2
20.3.3	<u>SLOPE</u>	20-2
20.3.4	<u>SIZE AND ALIGNMENTS</u>	20-3
20.3.5	<u>ADDITIONAL REQUIREMENTS</u>	20-4
20.4	MANHOLES	20-4
20.4.1	<u>LOCATION</u>	20-4
20.4.2	<u>TYPE</u>	20-4
20.4.3	<u>DIAMETER</u>	20-4
20.4.4	<u>FLOW CHANNEL</u>	20-5
20.4.5	<u>MATERIALS</u>	20-5
20.4.6	<u>CASTINGS</u>	20-5
20.4.7	<u>ACCESS</u>	20-5
20.5	SERVICE CONNECTIONS	20-5
20.5.1	<u>GENERAL</u>	20-5
20.5.2	<u>SIZE AND LENGTH</u>	20-5
20.5.3	<u>SLOPE</u>	20-6
20.5.4	<u>CONNECTION</u>	20-6
20.6	GREASE TRAPS	20-6
20.6.1	<u>GENERAL</u>	20-6
20.7	MATERIALS, INSTALLATION AND TESTING	20-6

SECTION 21

WASTEWATER FORCE MAINS

21.1	GENERAL CONSIDERATIONS	21-1
21.1.1	<u>DESIGN PERIOD</u>	21-1
21.1.2	<u>LOCATION</u>	21-1
21.2	DESIGN BASIS	21-1
21.2.1	<u>AVERAGE DAILY FLOW</u>	21-1
21.2.2	<u>PEAK DESIGN FLOW</u>	21-1
21.2.3	<u>DESIGN CALCULATIONS</u>	21-1
21.3	DETAILS OF DESIGN AND CONSTRUCTION	21-2
21.3.1	<u>VELOCITY AND DIAMETER</u>	21-2
21.3.2	<u>DESIGN FRICTION LOSSES</u>	21-2
21.3.3	<u>DESIGN PRESSURE AND RESTRAINT</u>	21-2
21.3.4	<u>TERMINATION</u>	21-2
21.3.5	<u>AIR RELEASE AND VACUUM RELIEF VALVES</u>	21-2
21.3.6	<u>AERIAL CROSSINGS</u>	21-3
21.3.7	<u>UNDERWATER CROSSINGS</u>	21-4
21.3.8	<u>VALVES</u>	21-4
21.4	MATERIAL, INSTALLATION AND TESTING	21-4
21.5	LOCATION AND IDENTIFICATION	21-4
21.6	ADDITIONAL REQUIREMENTS	21-4

SECTION 22

WASTEWATER PUMP STATIONS

22.1	GENERAL CONSIDERATIONS	22-1
22.2	DESIGN BASIS	22-1
22.2.1	<u>DESIGN FLOWS</u>	22-1
22.2.2	<u>NUMBER OF PUMPS</u>	22-1
22.2.3	<u>PUMP AND MOTOR SELECTION</u>	22-2
22.2.4	<u>DESIGN CALCULATIONS</u>	22-2
22.3	DETAILS OF DESIGN AND CONSTRUCTION	22-2
22.3.1	<u>FLOODING</u>	22-2
22.3.2	<u>ACCESSIBILITY</u>	22-2
22.3.3	<u>BUOYANCY</u>	22-2
22.3.4	<u>PUMP REQUIREMENTS</u>	22-3

22. 3. 5	WET WELL REQUIREMENTS	22-3
22. 3. 6	PUMP STATION WATER SYSTEM.....	22-3
22. 3. 7	ELECTRICAL EQUIPMENT, POWER SUPPLY AND POWER CORDS.....	22-4
22. 3. 8	CONTROLS	22-4
22. 3. 9	SITE SIZING AND EASEMENT REQUIREMENTS.....	22-4
22. 3. 10	SITE FENCING.....	22-4
22. 4	FLOW METERS	22-4
22. 5	EMERGENCY OPERATION.....	22-4

SECTION 23

WATER MAINS

23. 1	GENERAL CONSIDERATIONS	23-1
23. 1. 1	TYPE OF WATER MAINS	23-1
23. 1. 2	DESIGN PERIOD	23-1
23. 1. 3	LOCATION	23-1
23. 2	DESIGN BASIS.....	23-1
23. 2. 1	AVERAGE DAILY FLOW AND PEAK FLOWS	23-1
23. 2. 2	FIRE FLOW REQUIREMENTS.....	23-2
23. 2. 3	DESIGN CALCULATIONS	23-2
23. 3	DETAILS OF DESIGN AND CONSTRUCTION.....	23-2
23. 3. 1	PRESSURE.....	23-2
23. 3. 2	DIAMETER	23-2
23. 3. 3	FIRE HYDRANT LOCATION AND SPACING	23-3
23. 3. 4	DEAD ENDS	23-3
23. 3. 5	VALVES.....	23-3
23. 3. 6	SEPARATION OF WATER MAINS AND SEWERS	23-3
23. 3. 7	SURFACE WATER CROSSINGS	23-3
23. 3. 8	AIR RELIEF VALVES	23-4
23. 3. 9	CHAMBER DRAINAGE.....	23-4
23. 3. 10	DISINFECTION FOLLOWING REPAIR OR REPLACEMENT	23-4
23. 4	WATER SERVICES AND CONNECTIONS	23-4
23. 5	WATER METERING	23-4
23. 5. 1	GENERAL.....	23-4
23. 5. 2	SINGLE FAMILY, DUPLEX, AND MULTI- FAMILY SUBDIVISIONS WITH PUBLIC	

	<u>RIGHTS-OF-WAY</u>	23-4
23. 5. 3	<u>SINGLE FAMILY AND DUPLEX SUBDIVISIONS WITH PRIVATE STREETS</u>	23-5
23. 5. 4	<u>COMMERCIAL, INDUSTRIAL, AND INSTITUTIONAL PROJECTS WITHOUT PRIVATE FIRE LINES</u>	23-5
23. 5. 5	<u>COMMERCIAL, INDUSTRIAL, INSTITUTIONAL, MULTI-FAMILY WITH PRIVATE STREETS, APARTMENTS, AND CONDOMINIUM PROJECTS WITH PRIVATE FIRE LINES</u>	23-5
23. 5. 6	<u>SHOPPING CENTERS</u>	23-5
23. 5. 7	<u>METER INSTALLATION</u>	23-5
23. 5. 8	<u>METER SIZING</u>	23-6
23. 6	MATERIAL, INSTALLATION AND TESTING	23-6
23. 7	LOCATION AND IDENTIFICATION	23-6
23. 8	CROSS CONNECTION CONTROL	23-6
23. 8. 1	<u>GENERAL</u>	23-6
23. 8. 2	<u>COMMERCIAL, INDUSTRIAL AND MULTI-FAMILY RESIDENTIAL</u>	23-6
23. 8. 3	<u>IRRIGATION SYSTEMS</u>	23-6
23. 8. 4	<u>LOCATION AND INSTALLATION</u>	23-7

SECTION 30

GENERAL

30. 1	GRADES, SURVEY LINES, AND PROTECTION OF MONUMENTS	30-1
30. 1. 1	<u>GRADE</u>	30-1
30. 1. 2	<u>SURVEYS</u>	30-1
30. 1. 3	<u>MONUMENT PRESERVATION</u>	30-1
30. 2	UTILITY COORDINATION	30-1
30. 2. 1	<u>LOCATION OF UTILITIES</u>	30-1
30. 2. 2	<u>DEVIATIONS OCCASIONED BY STRUCTURES OR UTILITIES</u>	30-2
30. 2. 3	<u>TEST PITS</u>	30-2
30. 3	MAINTENANCE OF TRAFFIC AND CLOSING	

OF STREETS	30-2
30. 4 PROTECTION OF PUBLIC AND PROPERTY	30-3
30. 4. 1 <u>BARRICADES, GUARDS AND SAFETY</u> <u>PROVISIONS</u>	30-3
30. 4. 2 <u>PROTECTION OF UTILITY STRUCTURES</u>	30-3
30. 4. 3 <u>OPEN EXCAVATION</u>	30-4
30. 4. 4 <u>PROTECTION OF TREES AND SHRUBS</u>	30-4
30. 4. 5 <u>PROTECTION OF LAWN AREAS</u>	30-4
30. 4. 6 <u>RESTORATION OF FENCES</u>	30-4
30. 4. 7 <u>PROTECTION AGAINST SILTATION AND</u> <u>BANK EROSION</u>	30-4
30. 5 ACCESS TO THE PUBLIC SERVICES	30-5
30. 6 PUBLIC NUISANCE	30-5
30. 7 CONSTRUCTION HOURS	30-5
30. 8 CONSTRUCTION IN EASEMENTS AND RIGHTS-OF-WAY	30-5
30. 8. 1 <u>CONSTRUCTION IN EASEMENTS</u>	30-5
30. 8. 2 <u>CONSTRUCTION IN FLORIDA</u> <u>DEPARTMENT OF TRANSPORTATION</u> <u>RIGHT-OF-WAY</u>	30-6
30. 8. 3 <u>CONSTRUCTION IN LAKE COUNTY</u> <u>RIGHT-OF-WAY</u>	30-6
30. 8. 4 <u>CONSTRUCTION IN CITY OF MASCOTTE</u> <u>RIGHT-OF-WAY</u>	30-6
30. 9 SUSPENSION OF WORK DUE TO WEATHER	30-6
30. 10 USE OF CHEMICALS	30-6
30. 11 COOPERATION WITH OTHER CONTRACTORS	30-6
30. 12 SUBSURFACE EXPLORATION	30-7
30. 13 CLEANING	30-7
30. 13. 1 <u>DURING CONSTRUCTION</u>	30-7
30. 13. 2 <u>FINAL CLEANING</u>	30-7
30. 14 SALVAGE	30-7
30. 15 SHOP DRAWINGS AND SAMPLES	30-7

SECTION 31

SITE PREPARATION, SURFACE REMOVAL AND RESTORATION

31.1	GENERAL	31-1
31.2	CLEARING AND GRUBBING	31-1
31.2.1	<u>CLEARING</u>	31-1
31.2.2	<u>GRUBBING</u>	31-1
31.2.3	<u>STRIPPING</u>	31-1
31.2.4	<u>DISPOSAL OF CLEARED AND GRUBBED MATERIAL</u>	31-1
31.3	DUST CONTROL	31-2
31.4	SURFACE REMOVAL	31-2
31.5	RESTORATION	31-2

SECTION 32

EXCAVATION, BACKFILL, COMPACTION AND GRADING

32.1	GENERAL	32-1
32.2	SOIL BORINGS AND SUBSURFACE INVESTIGATIONS	32-1
32.3	EXISTING UTILITIES	32-1
32.4	MATERIALS	32-1
32.4.1	<u>GENERAL</u>	32-1
32.4.2	<u>STRUCTURAL FILL</u>	32-2
32.4.3	<u>COMMON FILL</u>	32-2
32.4.4	<u>SELECT COMMON FILL</u>	32-2
32.4.5	<u>BEDDING ROCK</u>	32-2
32.5	SHEETING AND BRACING IN EXCAVATIONS	32-2
32.5.1	<u>GENERAL</u>	32-2
32.5.2	<u>MISCELLANEOUS REQUIREMENTS</u>	32-3
32.6	DEWATERING, DRAINAGE AND FLOTATION	32-3
32.6.1	<u>GENERAL</u>	32-3
32.6.2	<u>ADDITIONAL REQUIREMENTS</u>	32-4
32.7	EXCAVATION	32-5
32.7.1	<u>GENERAL</u>	32-5
32.7.2	<u>EXCAVATION FOR STRUCTURES</u>	32-6

32. 7. 3	<u>TRENCH EXCAVATION</u>	32-6
32. 8	BEDDING AND BACKFILL	32-6
32. 8. 1	<u>GENERAL</u>	32-6
32. 8. 2	<u>BEDDING AND BACKFILL FOR STRUCTURES</u>	32-7
32. 8. 3	<u>BEDDING AND BACKFILL FOR PIPES</u>	32-8
32. 9	COMPACTION	32-9
32. 9. 1	<u>GENERAL</u>	32-9
32. 9. 2	<u>PERCENTAGE OF MAXIMUM DENSITY REQUIREMENTS</u>	32-9
32. 9. 3	<u>COMPACTION TESTS</u>	32-9
32. 10	GRADING	32-10
32. 11	MAINTENANCE	32-10
32. 12	INSPECTION AND QUALITY ASSURANCE	32-10
32. 12. 1	<u>INSPECTION</u>	32-10
32. 12. 2	<u>QUALITY ASSURANCE</u>	32-10

SECTION 33

BORING AND JACKING

33. 1	GENERAL	33-1
33. 2	PIPE MATERIAL	33-1
33. 2. 1	<u>STEEL CASING</u>	33-1
33. 2. 2	<u>CARRIER PIPE</u>	33-2
33. 2. 3	<u>INSPECTION</u>	33-2
33. 3	PIPE HANDLING	33-2
33. 4	CONSTRUCTION REQUIREMENTS	33-2
33. 4. 1	<u>WORK COORDINATION</u>	33-2
33. 4. 3	<u>DEWATERING</u>	33-2
33. 4. 4	<u>CARRIER PIPE SUPPORT</u>	33-3
33. 4. 5	<u>JACKING PITS</u>	33-3
33. 4. 6	<u>MISCELLANEOUS REQUIREMENTS</u>	33-3

SECTION 34

PRESSURE PIPE RESTRAINT

34.1	GENERAL	34-1
34.2	THRUST BLOCK CONSTRUCTION	34-1
34.3	RESTRAINED JOINT CONSTRUCTION	34-1
34.4	MECHANICAL RESTRAINING DEVICES	34-2
34.4.1	<u>GENERAL</u>	34-2
34.4.2	<u>JOINT RESTRAINT DEVICE</u>	34-2

SECTION 35

PRESSURE CONNECTION

35.1	GENERAL	35-1
35.2	TAPPING SLEEVES	35-1
35.2.1	<u>GENERAL</u>	35-1
35.2.2	<u>MECHANICAL JOINT SLEEVES</u>	35-1
35.2.3	<u>STEEL TAPPING SLEEVES</u>	35-1
35.2.4	<u>TAPPING VALVES</u>	35-1
35.3	NOTIFICATION AND CONNECTION TO EXISTING MAINS	35-1
35.4	INSTALLATION	35-2
35.4.1	<u>EXCAVATION, BACKFILL, COMPACTION AND GRADING</u>	35-2
35.4.2	<u>CONSTRUCTION DETAILS</u>	35-2

SECTION 40

PIPE MATERIAL FOR GRAVITY SEWERS

40.1	GENERAL	40-1
40.2	PIPE MATERIALS	40-1
40.2.1	<u>PVC GRAVITY SEWER PIPE</u>	40-1
40.2.2	<u>DIP GRAVITY SEWER PIPE</u>	40-1

40. 2. 3	REINFORCED CONCRETE PIPE	40-2
40. 2. 4	PIPE MARKINGS	40-2
40. 3	JOINT MATERIALS	40-2
40. 3. 1	PVC PIPE.....	40-2
40. 3. 2	DUCTILE IRON PIPE	40-2
40. 3. 3	CONCRETE PIPE	40-2
40. 3. 4	JOINTS FOR DISSIMILAR PIPE	40-2
40. 4	FITTINGS	40-2
40. 5	INSPECTION AND TESTING	40-3
40. 5. 1	GENERAL	40-3
40. 5. 2	MISCELLANEOUS INSPECTION AND TESTING REQUIREMENTS	40-3

SECTION 41

GRAVITY SEWER PIPE LAYING, JOINTING, AND MISCELLANEOUS CONSTRUCTION DETAILS

41. 1	SURVEY LINE AND GRADE	41-1
41. 2	PIPE PREPARATION AND HANDLING.....	41-1
41. 3	SEWER PIPE LAYING	41-1
41. 4	TRENCH PREPARATION AND PIPE BEDDING	41-2
41. 4. 1	TRENCH EXCAVATION, DEWATERING, BEDDING MATERIAL, BACKFILL, COMPACTION, FILL AND GRADING.....	41-2
41. 4. 2	PLACEMENT OF PIPE BEDDING MATERIAL.....	41-2
41. 4. 3	DEPTH OF BEDDING MATERIAL.....	41-2
41. 5	GRAVITY PIPE AND WATER MAIN SEPARATION.....	41-2
41. 6	PLUGS AND CONNECTIONS.....	41-2
41. 7	PIPE JOINTING.....	41-2

SECTION 42

MANHOLES

42. 1	GENERAL.....	42-1
--------------	---------------------	-------------

42. 2	PRE-CAST CONCRETE SECTIONS	42-1
42. 2. 1	<u>GENERAL</u>	42-1
42. 2. 2	<u>MISCELLANEOUS REQUIREMENTS</u>	42-1
42. 2. 3	<u>INSPECTION</u>	42-2
42. 3	CASTINGS	42-2
42. 4	CONSTRUCTION DETAILS	42-2
42. 4. 1	<u>BEDDING</u>	42-2
42. 4. 2	<u>CAST-IN-PLACE BASES</u>	42-3
42. 4. 3	<u>PRE-CAST MANHOLES</u>	42-3
42. 4. 4	<u>EXCAVATION AND BACKFILLING</u>	42-3
42. 4. 5	<u>PLACING CASTINGS</u>	42-3
42. 4. 6	<u>CHANNELS</u>	42-4
42. 4. 7	<u>PIPE CONNECTIONS</u>	42-4
42. 4. 8	<u>DROP MANHOLE CONNECTIONS</u>	42-4
42. 5	CLEANING	42-4
42. 6	INSPECTION FOR ACCEPTANCE	42-4

SECTION 43

SERVICE LATERALS

43. 1	GENERAL	43-1
43. 2	MATERIALS	43-1
43. 3	CONSTRUCTION DETAILS	43-1
43. 3. 1	<u>GENERAL</u>	43-1
43. 3. 2	<u>EXCAVATION AND BACKFILL</u>	43-1
43. 3. 3	<u>PIPE LAYING AND JOINTING</u>	43-2
43. 3. 4	<u>LINE AND GRADE</u>	43-2
43. 4	TERMINATION OF SERVICE LATERALS	43-2
43. 5	INSPECTION	43-2
43. 6	RESTORATION, FINISHING AND CLEANUP	43-2
43. 7	LOCATION	43-2

SECTION 44

TESTING AND INSPECTION FOR ACCEPTANCE OF GRAVITY SEWERS

44.1	GENERAL	44-1
44.2	TESTING FOR LEAKAGE	44-1
44.2.1	<u>TYPE OF TEST</u>	44-1
44.2.2	<u>SELECTION OF TEST SECTIONS</u>	44-1
44.2.3	<u>PREPARATION AND COORDINATION</u> <u>FOR TESTING</u>	44-1
44.2.4	<u>LEAKAGE TEST</u>	44-2
44.3	VIDEO INSPECTION FOR ALIGNMENT, DEFLECTION AND INTEGRITY	44-2

SECTION 45

WASTEWATER FORCE MAINS

45.1	GENERAL	45-1
45.2	PIPE INSPECTION AND TEST	45-1
45.3	PVC PIPE	45-1
45.3.1	<u>PVC PIPE</u>	45-1
45.3.2	<u>JOINTS</u>	45-1
45.3.3	<u>FITTINGS</u>	45-1
45.4	DUCTILE IRON PIPE AND FITTINGS	45-2
45.4.1	<u>DUCTILE IRON PIPE</u>	45-2
45.4.2	<u>FITTINGS</u>	45-2
45.4.3	<u>JOINTS</u>	45-2
45.4.4	<u>COATINGS AND LININGS</u>	45-2
45.4.5	<u>POLYETHYLENE ENCASEMENT</u>	45-3
45.5	PIPE HANDLING	45-3
45.6	AIR AND VACUUM RELEASE VALVES	45-3
45.6.1	<u>GENERAL</u>	45-3
45.6.2	<u>WASTEWATER AIR/VACUUM VALVE</u>	45-3
45.6.3	<u>WASTEWATER AIR RELEASE VALVE</u>	45-3
45.7	NOTIFICATION AND CONNECTION TO EXISTING MAINS	45-3
45.8	PLUG VALVES	45-4
45.8.1	<u>GENERAL</u>	45-4

45. 8. 2	<u>VALVE CONSTRUCTION</u>	45-4
45. 8. 3	<u>VALVE TESTING</u>	45-4
45. 8. 4	<u>ACTUATORS</u>	45-4
45. 9	VALVE BOXES	45-5
45. 10	SEPARATION OF FORCE MAINS AND WATER MAINS	45-5
45. 11	FORCE MAIN CONSTRUCTION	45-5
45. 12	HYDROSTATIC TESTS	45-5
45. 13	FINAL CLEANING	45-5
45. 14	LOCATION AND IDENTIFICATION	45-5

SECTION 46

WASTEWATER PUMP STATIONS

46. 1	GENERAL	46-1
46. 2	WET WELL AND VALVE VAULT	46-1
46. 3	ACCESS FRAMES AND COVERS	46-1
46. 4	PUMPS AND CONTROLS	46-1
46. 5	PIPING, VALVES AND ACCESSORIES	46-1
46. 5. 1	<u>PIPING</u>	46-1
46. 5. 2	<u>PLUG VALVES</u>	46-1
46. 5. 3	<u>CHECK VALVES</u>	46-1
46. 5. 4	<u>PRESSURE GAUGES</u>	46-2
46. 6	STANDBY POWER GENERATOR SYSTEM	46-2
46. 6. 1	<u>GENERAL</u>	46-2
46. 6. 2	<u>GENERATOR SET</u>	46-2
46. 7	FLOW MONITORING SYSTEM	46-8
46. 7. 1	<u>GENERAL</u>	46-8
46. 7. 2	<u>MAGNETIC FLOWMETER/TRANSMITTERS</u>	46-8
46. 7. 3	<u>ELECTRONIC RECORDING RECEIVER</u>	46-10
46. 7. 4	<u>WARRANTY AND SERVICE</u>	46-10
46. 8	CHAIN LINK FENCE	46-10
46. 8. 1	<u>GENERAL</u>	46-10
46. 8. 2	<u>MATERIALS</u>	46-11

46. 8. 3	<u>INSTALLATION</u>	46-11
46. 9	REQUIRED SUBMITTALS	46-12
46. 10	ELECTRICAL GROUNDING SYSTEM	46-13
46. 10. 1	<u>GENERAL</u>	46-13
46. 10. 2	<u>MATERIAL AND INSTALLATION</u>	46-13
46. 11	INSPECTION AND TESTING	46-14

SECTION 47

SUBMERSIBLE WASTEWATER PUMPS

47. 1	GENERAL	47-1
47. 2	PUMP CONSTRUCTION DETAILS	47-1
47. 2. 1	<u>SHAFT</u>	47-1
47. 2. 2	<u>IMPELLER</u>	47-1
47. 2. 3	<u>MECHANICAL SEAL</u>	47-2
47. 2. 4	<u>GUIDES</u>	47-2
47. 3	MOTORS	47-3
47. 3. 1	<u>GENERAL REQUIREMENTS</u>	47-3
47. 3. 2	<u>HEAT AND MOISTURE SENSORS</u>	47-3
47. 4	PUMP CONTROL SYSTEM	47-3
47. 5	SHOP PAINTING	47-4
47. 6	HANDLING	47-4
47. 7	WARRANTY	47-4

SECTION 48

PUMP STATION ELECTRICAL POWER AND CONTROL SYSTEM

48. 1	GENERAL	48-1
48. 2	PANEL CONSTRUCTION	48-1
48. 3	POWER SUPPLY AND MAIN DISCONNECT	48-2
48. 4	CIRCUIT BREAKERS	48-2

48. 4. 1	<u>MAIN BREAKERS</u>	48-3
48. 4. 2	<u>CIRCUIT BREAKERS</u>	48-3
48. 5	MOTOR CIRCUIT PROTECTORS	48-3
48. 6	MOTOR STARTER AND SELECTOR SWITCHES	48-3
48. 7	PUMP ALTERNATOR	48-3
48. 8	LIGHTS AND ALARMS	48-4
48. 8. 1	<u>INDICATOR LIGHTS</u>	48-4
48. 8. 2	<u>HIGH LEVEL ALARM</u>	48-4
48. 8. 3	<u>ALARM DIALER</u>	48-4
48. 9	ADDITIONAL REQUIREMENTS	48-4
48. 9. 1	<u>WIRING</u>	48-4
48. 9. 2	<u>TERMINAL POINTS</u>	48-4
48. 9. 3	<u>ENGRAVED NAMEPLATES</u>	48-5
48. 9. 4	<u>SURGE PROTECTOR</u>	48-5
48. 9. 5	<u>ELAPSED TIME METERS</u>	48-5
48. 9. 6	<u>CONVENIENCE RECEPTACLE</u>	48-5
48. 9. 7	<u>CONTROL TERMINAL BLOCKS</u>	48-5
48. 9. 8	<u>CONTROL POWER TRANSFORMERS</u>	48-5
48. 9. 9	<u>CONTROL RELAY</u>	48-6
48. 9.10	<u>ELECTRICAL SCHEMATIC</u>	48-6
48. 9.11	<u>PHASE MONITOR</u>	48-6
48. 10	TESTING, SERVICE AND WARRANTY	48-6
48. 10. 1	<u>TESTING</u>	48-6
48. 10. 3	<u>WARRANTY</u>	48-6

DIVISION V - WATER DISTRIBUTION

SECTION 50

PIPE MATERIAL FOR WATER MAINS AND SERVICE CONNECTIONS

50. 1	GENERAL	50-1
50. 2	PIPE INSPECTION AND TESTING	50-1
50. 3	PVC PIPE	50-1
50. 3. 1	<u>PVC PIPE</u>	50-1
50. 3. 2	<u>JOINTS</u>	50-1
50. 3. 3	<u>FITTINGS</u>	50-1

50. 4	DUCTILE IRON PIPE AND FITTINGS	50-2
50. 4. 1	<u>DUCTILE IRON PIPE</u>	50-2
50. 4. 2	<u>FITTINGS</u>	50-2
50. 4. 3	<u>JOINTS</u>	50-2
50. 4. 4	<u>COATINGS AND LININGS</u>	50-2
50. 4. 5	<u>POLYETHYLENE ENCASEMENT</u>	50-2
50. 5	SERVICE PIPE, STOPS, FITTINGS, AND SERVICE SADDLES	50-3
50. 5. 1	<u>SERVICE PIPE</u>	50-3
50. 5. 2	<u>CORPORATION STOPS</u>	50-3
50. 5. 3	<u>FITTINGS</u>	50-3
50. 5. 4	<u>SERVICE SADDLES</u>	50-3

SECTION 51

PIPE INSTALLATION FOR WATER MAINS

51. 1	GENERAL	51-1
51. 2	PIPE HANDLING	51-1
51. 3	SEPARATION OF WATER MAINS AND SEWERS	51-1
51. 3. 1	<u>GENERAL</u>	51-1
51. 3. 2	<u>HORIZONTAL SEPARATION</u>	51-1
51. 3. 3	<u>VERTICAL SEPARATION</u>	51-2
51. 3. 4	<u>CROSSING OF WATER MAINS AND SEWERS</u>	51-2
51. 4	TRENCH PREPARATION AND PIPE BEDDING	51-2
51. 4. 1	<u>TRENCH PREPARATION AND PIPE BEDDING</u>	51-2
51. 4. 2	<u>PIPE PREPARATION AND HANDLING</u>	51-2
51. 4. 3	<u>TRENCH DEWATERING</u>	51-3
51. 4. 4	<u>SURVEY LINE AND GRADE</u>	51-3
51. 4. 5	<u>PIPE LAYING IN TRENCH</u>	51-3
51. 4. 6	<u>LAYING PVC PIPE</u>	51-3
51. 4. 7	<u>LAYING DUCTILE IRON PIPE</u>	51-3
51. 4. 8	<u>LAYING OF PIPES ON CURVES</u>	51-4
51. 4. 9	<u>PIPE RESTRAINING AND THRUST BLOCK</u>	51-4
51. 4. 10	<u>BEDDING AND BACKFILL FOR PIPES</u>	51-4
51. 5	HYDROSTATIC TESTS	51-4
51. 5. 1	<u>GENERAL</u>	51-4
51. 5. 2	<u>TESTING CRITERIA</u>	51-5
51. 5. 3	<u>PROCEDURE FOR PRESSURE TEST</u>	51-5
51. 5. 4	<u>PROCEDURE FOR LEAKAGE TEST</u>	51-5

51. 6	DISINFECTION OF WATER MAINS	51-6
51. 6. 1	<u>GENERAL</u>	51-6
51. 6. 2	<u>FLUSHING</u>	51-6
51. 6. 3	<u>DISINFECTION CRITERIA</u>	51-6
51. 6. 4	<u>FORM OF APPLIED CHLORINE</u>	51-6
51. 6. 5	<u>POINT OF APPLICATION</u>	51-6
51. 6. 6	<u>OPERATION OF CITY VALVES</u>	51-7
51. 6. 7	<u>RETENTION PERIOD</u>	51-7
51. 6. 8	<u>CHLORINATING VALVES AND HYDRANTS</u>	51-7
51. 6. 9	<u>FINAL FLUSHING AND TESTING</u>	51-7
51. 6.10	<u>REPETITION OF FLUSHING AND TESTING</u>	51-7
51. 7	NOTIFICATION AND CONNECTION TO EXISTING MAINS.....	51-8
51. 8	WATER SERVICE PIPING CONNECTION	51-8
51. 9	LOCATION AND IDENTIFICATION	51-8

SECTION 52

VALVES, HYDRANTS AND ACCESSORIES FOR WATER MAINS

52. 1	GENERAL.....	52-1
52. 2	RESILIENT SEAT GATE VALVES.....	52-1
52. 2. 1	<u>GENERAL</u>	52-1
52. 2. 2	<u>MATERIAL</u>	52-1
52. 2. 3	<u>MISCELLANEOUS REQUIREMENTS</u>	52-1
52. 3	BUTTERFLY VALVES.....	52-1
52. 3. 1	<u>GENERAL</u>	52-1
52. 3. 2	<u>MATERIAL</u>	52-2
52. 3. 3	<u>FACE TO FACE DIMENSION</u>	52-2
52. 3. 4	<u>VALVE SHAFT</u>	52-2
52. 3. 5	<u>VALVE OPERATOR</u>	52-2
52. 4	VALVE INSTALLATION.....	52-2
52. 5	VALVE BOXES	52-3
52. 6	AIR RELEASE VALVES	52-3
52. 7	FIRE HYDRANTS.....	52-3
52. 7. 1	<u>MATERIAL</u>	52-3

52. 7. 2	<u>PAINING</u>	52-4
52. 7. 3	<u>CONSTRUCTION DETAILS</u>	52-4
52. 7. 4	<u>LOCATION</u>	52-4
52. 7. 5	<u>REFLECTIVE PAVEMENT MARKERS</u>	52-4

APPENDICES

<u>WASTEWATER EQUIVALENT RESIDENTIAL</u> <u>UNIT DETERMINATION</u>	A-1
<u>WATER EQUIVALENT RESIDENTIAL UNIT</u> <u>DETERMINATION</u>	B-1
<u>MAINTENANCE, MATERIALS & WORKMANSHIP</u> <u>WARRANTY BOND</u>	C-1
<u>BILL OF SALE</u>	C-3
<u>CERTIFICATE OF COMPLETION</u>	C-4
<u>APPROVAL FOR MAINTENANCE</u>	C-5
<u>WASTEWATER MAIN MATERIALS</u>	D-1
<u>WASTEWATER PUMP STATION MATERIALS</u>	D-4
<u>WATER MAIN MATERIALS</u>	D-7
<u>STANDARD DETAIL DRAWINGS</u>	